



REQUEST FOR PROPOSALS ADDENDUM

RFP-DPW-2025-0006

Cortez Blvd (SR 50) Pump Station Replacement Project

\*\*\*\*\*

ADDENDUM #7

Date Issued: April 17, 2025

\*\*\*\*\*

TO: All prospective proposers:

You are hereby notified that this Addendum shall be attached to and made a part of the above-named solicitation and contract documents, as follows:

**UPDATED Bid Tabulation Form**

**PLEASE NOTE: THIS FORM REPRESENTS ENGINEERING ESTIMATES ONLY!  
CONTRACTORS MUST PROVIDE/CONFIRM ALL AMOUNTS AND QUANTITIES.**

\*\*\*REMAINDER OF PAGE LEFT BLANK\*\*\*

**CORTEZ BOULEVARD PUMP STATION REPLACEMENT PROJECT**

**ENGINEERING ESTIMATES ONLY - CONTRACTOR MUST PROVIDE/CONFIRM ALL AMOUNTS & QUANTITIES**

ITEM	DESCRIPTION	ESTIMATED QUANTITY	UNIT PRICE	AMOUNT
LS=Lump Sum, EA=Each, LF=Linear Foot, SF=Square Foot, CY=Cubic Yard, SY=Square Yard				
<b>I. GENERAL CONDITIONS</b>				
1	Mobilization	1	LS	
2	Insurance, Permits, & Performance and Payment Bond	1	LS	
3	Maintenance of Traffic	1	LS	
4	Survey Layout/As-built	1	LS	
5	Erosion Sediment Control (incl. NPDES Permit/insp rpt./NOT)	1	LS	
6	Construction Material Testing	1	LS	
7	Pre/Post Video	1	LS	
8	Pump Station Site Demo and Grading	1	LS	
9	Temporary Bypass Pumping	1	LS	
10	Refurbish Existing Wet Well	1	LS	
11	Clear and Grub 20'x108' to existing Manhole behind LS site	108	LF	
12	Restore Area of Clear and Grub, 20'x108'	2,160	SF	
13	Manhole Rehabilitation	1	LS	
14	Replace Existing Manhole Frame & Covers w/ Composite	1	EA	
15	Connect 8" Gravity Main to Existing Manhole	1	EA	
16	Replace existing pumps with Tri-plex pump system including rails, wiring, piping, valves, fittings, core drill conduits, etc. in Wet Well & Valve Vault	1	LS	
17	Precast Valve Vault and Lid with 6'x10' Access Hatch	1	LS	
18	5-ft Diameter Concrete Doghouse Manhole w/traffic bearing cover, ~17.85' Deep, F&I, (Including any Sheeting, Shoring, or Dewatering)	1	LS	
19	6-ft Diameter Concrete Manhole w/traffic bearing cover, ~ 17.00" Deep, F&I, (Including any Sheeting, Shoring, or Dewatering)	1	LS	

**CORTEZ BOULEVARD PUMP STATION REPLACEMENT PROJECT**

**ENGINEERING ESTIMATES ONLY - CONTRACTOR MUST PROVIDE/CONFIRM ALL AMOUNTS & QUANTITIES**

ITEM	DESCRIPTION	ESTIMATED QUANTITY		UNIT PRICE	AMOUNT
20	Pump Station Electrical Control Panels & Lighting	1	LS		
21	Remove existing 12-inch FM	1	LS		
22	8" PVC C-900 DR26	44	LF		
23	24" PVC C-900 DR26	45	LF		
24	8" DI Pipe, MJ, RJ	20	LF		
25	8" 45-Deg Elbow, DIP, MJ, RJ	2	EA		
26	8" 90-Deg Elbow, DIP, MJ, RJ	5	EA		
27	12" PVC C-900 DR18 FM	20	LF		
28	8" 316 SS, Sch 40	20	LF		
29	8" 90 Deg-Elbow, 316 SS, Sch 40	1	EA		
30	12"x8" TEE, DIP (MJ), RJ	1	EA		
31	8" Gate Valve Assembly (MJ) with Valve Pad (In Driveway)	2	EA		
32	12" 45 Deg Elbow , MJ, RJ	2	EA		
33	Connect to Existing 12" FM	1	LS		
34	6" (3,000 PSI w/ Fibermesh) Concrete Driveway	3,035	SF		
35	6 " #57 Stone	200	CY		
36	6-FT High, Galvanized Interwoven Fence w/Cantilever Slide Gate and Swing Gate	1	LS		
37	Relocate Water Service and Backflow Preventer	1	LS		
38	Sod Restoration of Disturbed Areas	240	SY		
				<b>SUBTOTAL</b>	
<b>SUMMARY</b>					
<b>SUBTOTAL</b>					
				<b>ITEM TOTAL</b>	